

PROJECT ESTIMATION REPORT

Project: TEST
Date: February 17, 2026

Elev 1

PROFILES

Description	Part Number	Total Quantity Required	Qty Per Elevation	Total List Cost	List Cost Per Elev	Discounted Total Cost	Discounted Per Elev
Vertical Sill/Jamb Screw Spline Assembly (Jamb) / Horizontal Sill/Jamb Screw Spline Assembly (Sill)	BE9-2513	8ft, 8ft, 8ft, 8ft, 3ft, 3ft, 3ft, 3ft, 3ft, 3ft	3ft x 4, 8ft x 2	\$1,257.00	\$838.00	\$719.00	\$479.34
Vertical Flush Filler	E9-2512	8ft x 6	8ft x 3	\$300.00	\$150.00	\$171.60	\$85.80
Vertical Two Piece Mullion Screw Spline Assembly	BE9-2511	8ft x 6	8ft x 3	\$994.00	\$497.00	\$568.57	\$284.28
Horizontal Horizontal Screw Spline Assembly	BE9-2515	3ft x 8	3ft x 4	\$527.00	\$527.00	\$301.44	\$301.44
Horizontal Head	BE9-2514	3ft x 8	3ft x 4	\$444.00	\$444.00	\$253.97	\$253.97
Thermal Sill Flashing	BE9-2578	12ft x 2	12ft x 1	\$264.00	\$264.00	\$151.01	\$151.01
Horizontal Glass Stop (Use with BE9-2514, BE9-2515, BE9-2517)	E9-2519	3ft x 16	3ft x 8	\$170.10	\$85.05	\$97.30	\$48.65
Total Profiles Cost				\$3,956.10	\$2,805.05	\$2,262.89	\$1,604.49

Elevation Cost Summary

Category	Cost / Elevation	Total Elevation Cost
Profile Costs	\$1,604.49	\$2,262.89
Accessory Costs	\$449.71	\$480.77
Gasket Costs	\$231.66	\$231.66
Door Costs	\$1,638.00	\$3,276.00
Glass Costs	\$818.74	\$1,637.47
Fabrication Costs	\$360.00	\$720.00
Elev 1 Total	\$5,102.59	\$8,608.79

Elev 2

ACCESSORIES

Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total Cost
End Dam For Sill Flashing	E1-0199	2.00 pcs	\$64.80	\$37.07
Water Deflector	E2-0047	8.00 pcs	\$119.00	\$68.07
#12 x 1-1/4" PHSMS Type AB, Zinc Plated Steel, For Screw Spline Attachment	PC-1220	56.00 pcs	\$18.30	\$10.47
#10-24 x 3/8" PHMS, Stainless Steel, For Attachment of Sill to Sill Flashing	PM-1006-SS	12.00 pcs	\$46.65	\$26.68
#12 x 3/4" UFHSMS Type A, Zinc Plated Steel For End Dam Attachment	UA-1212	4.00 pcs	\$48.60	\$27.80
Setting Block Chair Use with E2-0177 Setting Block at Sill	E1-2530	8.00 pcs	\$36.00	\$20.59
Side Block For Intermediate Vertical Shallow Pocket	E2-0166	6.00 pcs	\$76.95	\$44.02
Setting Block For Sill	E2-0177	8.00 pcs	\$76.95	\$44.02
1-1/8" "W" Side Block For Jamb	E2-0545	4.00 pcs	\$147.00	\$84.08
1/2" "W" Side Block For Intermediate Vertical Deep Pocket	E2-0154	6.00 pcs	\$56.70	\$32.43
Setting Block For Intermediate Horizontal	E2-0611	8.00 pcs	\$95.25	\$54.48
Total Accessories Cost			\$786.20	\$449.71

Elevation Cost Summary

Category	Total Elevation Cost
Profile Costs	\$1,604.49
Accessory Costs	\$449.71
Gasket Costs	\$231.66
Glass Costs	\$879.38
Fabrication Costs	\$360.00
Elev 2 Total	\$3,525.23

Elev 3

System Input

Item	Value
System Input	YES 45TU FRONT SET(OG)
Finish	Clear
Elevation Type	Elev 3
Total Count	3
Bays Wide	3
Bays Tall	3
Custom Bay Widths	10.00 in, 67.00 in, 67.00 in
Custom Bay Heights	38.00 in, 20.00 in, 38.00 in
Opening Width	144.00 in
Opening Height	96.00 in
Sq Ft per Type	96.00 sqft
Total Sq Ft	288.00 sqft
Perimeter Ft	40.00 ft
Total Perimeter Ft	120.00 ft
Doors	6 x Wide Door (\$1,813.25) with: Latch Lock w/ Lever Handle, Extended Ladder Pull (Single)

GASKETS

Description	Part Number	Total Quantity Required	Qty Per Elevation	Total List Cost	List Cost Per Elev	Discounted Total Cost	Discounted Per Elev
Glazing Gasket For 1" Glazing	E2-0052	720.00 ft	720.00 ft x 1	\$810.00	\$405.00	\$463.32	\$231.66
Total Gaskets Cost				\$810.00	\$405.00	\$463.32	\$231.66

DOORS

Description	Part Number	Total Quantity Required	Qty Per Elevation	Total List Cost	List Cost Per Elev	Discounted Total Cost	Discounted Per Elev
Door (3' X 7')	N/A	6.00 pcs	2.00 pcs	\$10,879.50	\$3,626.50	\$10,879.50	\$3,626.50
Total Doors Cost				\$10,879.50	\$3,626.50	\$10,879.50	\$3,626.50

GLASS

Description	Part Number	Total Quantity Required	Qty Per Elevation	Total List Cost	List Cost Per Elev	Discounted Total Cost	Discounted Per Elev
Glass Area (Adjusted)	N/A	194.96 sqft	64.99 sqft	\$2,047.12	\$682.37	\$2,047.12	\$682.37
Total Glass Cost				\$2,047.12	\$682.37	\$2,047.12	\$682.37

FABRICATION

Description	Part Number	Total Quantity Required	Qty Per Elevation	Total List Cost	List Cost Per Elev	Discounted Total Cost	Discounted Per Elev
Door Area (to subtract from glass)	N/A	126.00 sqft	42.00 sqft	\$0.00	\$0.00	\$0.00	\$0.00
Joints Fabrication Labor	N/A	72.00 joints	24.00 joints	\$1,080.00	\$360.00	\$1,080.00	\$360.00
Total Fabrication Cost				\$1,080.00	\$360.00	\$1,080.00	\$360.00

SUMMARY

PROFILES

Description	Project Total Materials	Total Feet Required	Sticks Required	Total Quantity Required	Total List Cost	Discounte d Total Cost	Residual Qty	Waste %	Residual Cost
Vertical Sill/Jamb Screw Spline Assembly (Jamb)	BE9-2513 (clear)	168.00 ft	7 (24ft per)	8ft x12, 6ft x6, 3ft x12, 1ft x3	\$2,933.00	\$1,800.86	0.00 ft	0.00%	\$0.00
Vertical Flush Filler	E9-2512 (clear)	120.00 ft	5 (24ft per)	8ft x15	\$750.00	\$460.50	0.00 ft	0.00%	\$0.00
Vertical Two Piece Mullion Screw Spline Assembly	BE9-2511 (clear)	120.00 ft	5 (24ft per)	8ft x15	\$2,485.00	\$1,525.79	0.00 ft	0.00%	\$0.00
Horizontal Horizontal Screw Spline Assembly	BE9-2515 (clear)	72.00 ft	3 (24ft per)	6ft x6, 3ft x12, 1ft x3	\$1,581.00	\$970.73	0.00 ft	0.00%	\$0.00
Horizontal Head	BE9-2514 (clear)	72.00 ft	3 (24ft per)	6ft x6, 3ft x12, 1ft x3	\$1,332.00	\$817.85	0.00 ft	0.00%	\$0.00
Thermal Sill Flashing	BE9-2578 (clear)	72.00 ft	3 (24ft per)	12ft x6	\$792.00	\$486.29	0.00 ft	0.00%	\$0.00
Horizontal Glass Stop (Use with BE9-2514, BE9-2515, BE9-2517)	E9-2519 (clear)	180.00 ft	8 (24ft per)	6ft x18, 3ft x24, 1ft x9	\$680.40	\$417.77	12ft x1	6.25%	\$26.11
Total Profiles Cost					\$10,553.40	\$6,479.79			\$26.11

ACCESSORIES

Description	Project Total Materials	Total Pieces Required	Qty Per Order	Orders Required	Total List Cost	Discounted Total Cost	Residual Qty	Waste %	Residual Cost
End Dam For Sill Flashing	E1-0199	12.00 pcs	20 pcs per	1 order	\$64.80	\$39.79	8.00 pcs	40.00%	\$15.91
Water Deflector	E2-0047	42.00 pcs	50 pcs per	1 order	\$119.00	\$73.07	8.00 pcs	16.00%	\$11.69
#12 x 1-1/4" PHSMS Type AB, Zinc Plated Steel, For Screw Spline Attachment	PC-1220	348.00 pcs	100 pcs per	4 orders	\$73.20	\$44.94	52.00 pcs	13.00%	\$5.84
#10-24 x 3/8" PHMS, Stainless Steel, For Attachment of Sill to Sill Flashing	PM-1006-SS	63.00 pcs	100 pcs per	1 order	\$46.65	\$28.64	37.00 pcs	37.00%	\$10.60
#12 x 3/4" UFHSMS Type A, Zinc Plated Steel For End Dam Attachment	UA-1212	24.00 pcs	100 pcs per	1 order	\$48.60	\$29.84	76.00 pcs	76.00%	\$22.68
Setting Block Chair Use with E2-0177 Setting Block at Sill	E1-2530	42.00 pcs	1 pcs per	42 orders	\$189.00	\$116.05	0.00 pcs	0.00%	\$0.00
Side Block For Intermediate Vertical Shallow Pocket	E2-0166	36.00 pcs	50 pcs per	1 order	\$76.95	\$47.25	14.00 pcs	28.00%	\$13.23
Setting Block For Sill	E2-0177	42.00 pcs	50 pcs per	1 order	\$76.95	\$47.25	8.00 pcs	16.00%	\$7.56
1-1/8" "W" Side Block For Jamb	E2-0545	30.00 pcs	50 pcs per	1 order	\$147.00	\$90.26	20.00 pcs	40.00%	\$36.10
1/2" "W" Side Block For Intermediate Vertical Deep Pocket	E2-0154	36.00 pcs	50 pcs per	1 order	\$56.70	\$34.81	14.00 pcs	28.00%	\$9.75
Setting Block For Intermediate Horizontal	E2-0611	42.00 pcs	50 pcs per	1 order	\$95.25	\$58.48	8.00 pcs	16.00%	\$9.36
Total Accessories Cost					\$994.10	\$610.38			\$142.72

GASKETS

Description	Project Total Materials	Total Feet Required	Rolls Required	Total Quantity Required	Total List Cost	Discounted Total Cost	Residual Qty	Waste %	Residual Cost
Glazing Gasket For 1" Glazing	E2-0052 (clear)	1392.00 ft	3 (500ft per)	720ft x1, 448ft x1, 224ft x1	\$1,215.00	\$746.01	276ft x1, 52ft x1	19.07%	\$163.13
Total Gaskets Cost					\$1,215.00	\$746.01			\$163.13

DOORS

Description	Project Total Materials	Unit Price	Total Quantity Required	Total List Cost	Discounted Total Cost	Residual Qty	Waste %	Residual Cost
Door (3' X 7')	Door (3' X 7')	\$1769.44	8.00 pcs	\$14,155.50	\$14,155.50	N/A	N/A	\$0.00
Total Doors Cost				\$14,155.50	\$14,155.50			\$0.00

GLASS

Description	Project Total Materials	Unit Price	Total Quantity Required	Total List Cost	Discounted Total Cost	Residual Qty	Waste %	Residual Cost
Glass Area (Adjusted)	Glass Area (Adjusted)	\$10.50	434.66 sqft	\$4,563.97	\$4,563.97	N/A	N/A	\$0.00
Total Glass Cost				\$4,563.97	\$4,563.97			\$0.00

LABOR

Description	Project Total Materials	Unit Price	Total Quantity Required	Total List Cost	Discounted Total Cost	Residual Qty	Waste %	Residual Cost
Joints Fabrication Labor	Joints Fabrication Labor	\$15.00	144.00 joints	\$2,160.00	\$2,160.00	N/A	N/A	\$0.00
Total Labor Cost				\$2,160.00	\$2,160.00			\$0.00

ELEVATION SUMMARY

Elevation	Quantity	Dimensions	SQFT Total	Perimeter FT
Elev 2	1	144.0" x 96.0"	96.00	40.00
Elev 1	2	144.0" x 96.0"	192.00	80.00
Elev 3	3	144.0" x 96.0"	288.00	120.00
TOTAL	6		576.00	240.00

COST OVERVIEW

Item	Value
List Price Total	\$33,641.96
Discounted Total	\$28,715.64
Residual / Waste Cost	\$331.96
Waste Percentage	1.16%

PROJECT TOTAL

Item	Amount
Discounted Total	\$28,715.64
GRAND TOTAL	\$28,715.64