

PROJECT ESTIMATION REPORT

Project: Test Report
Date: January 17, 2026

Elevation 2

System Input

Item	Value
System Input	YES 45TU FRONT SET(OG)
Finish	Black
Elevation Type	Elevation 2
Total Count	1.00
Bays Wide	3.00
Bays Tall	3.00
Custom Bay Widths	10.00 in, 20.00 in, 3.00 in
Custom Bay Heights	2.00 in, 2.00 in, 64.00 in
Opening Width	33.00 in
Opening Height	68.00 in
Sq Ft per Type	15.58 sqft
Total Sq Ft	15.58 sqft
Perimeter Ft	16.83 ft
Total Perimeter Ft	16.83 ft
Doors	None

PROFILES

Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total List Cost
Vertical Sill/Jamb Screw Spline Assembly (Jamb) / Horizontal Sill/Jamb Screw Spline Assembly (Sill)	BE9-2513	5.67ft, 5.67ft, 0.83ft, 1.67ft, 0.25ft	\$460.90	\$282.99
Vertical Flush Filler	E9-2512	5.67ft x 2	\$165.00	\$101.31

Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total List Cost
Vertical Two Piece Mullion Screw Spline Assembly	BE9-2511	5.67ft x 2	\$546.70	\$335.67
Horizontal Horizontal Screw Spline Assembly	BE9-2515	0.83ft, 1.67ft, 0.25ft	\$579.70	\$355.94
Horizontal Head	BE9-2514	0.83ft, 1.67ft, 0.25ft	\$488.40	\$299.88
Thermal Sill Flashing	BE9-2578	2.75 ft	\$290.40	\$178.31
Horizontal Glass Stop (Use with BE9-2514, BE9-2515, BE9-2517)	E9-2519	0.83ft, 1.67ft, 0.25ft, 0.83ft, 1.67ft, 0.25ft, 0.83ft, 1.67ft, 0.25ft	\$93.56	\$57.44
		Total Profile Cost	\$2,624.66	\$1,611.54

ACCESSORIES

Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total List Cost
End Dam For Sill Flashing	E1-0199	2.00 pcs	\$64.80	\$39.79
Water Deflector	E2-0047	6.00 pcs	\$119.00	\$73.07
#12 x 1-1/4" PHSMS Type AB, Zinc Plated Steel, For Screw Spline Attachment	PC-1220	60.00 pcs	\$18.30	\$11.24
#10-24 x 3/8" PHMS, Stainless Steel, For Attachment of Sill to Sill Flashing	PM-1006-SS	9.00 pcs	\$46.65	\$28.64
#12 x 3/4" UFHSMS Type A, Zinc Plated Steel For End Dam Attachment	UA-1212	4.00 pcs	\$48.60	\$29.84
Setting Block Chair Use with E2-0177 Setting Block at Sill	E1-2530	6.00 pcs	\$27.00	\$16.58
Setting Block For Sill	E2-0177	6.00 pcs	\$76.95	\$47.25
1-1/8" "W" Side Block For Jamb	E2-0545	6.00 pcs	\$147.00	\$90.26
1/2" "W" Side Block For Intermediate Vertical Deep Pocket	E2-0154	6.00 pcs	\$56.70	\$34.81
Setting Block For Intermediate Horizontal	E2-0611	6.00 pcs	\$95.25	\$58.48
		Total Accessory Cost	\$777.20	\$477.20

GASKETS

Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total List Cost
Glazing Gasket For 1" Glazing	E2-0052	101.00 ft	\$405.00	\$248.67
		Total Gasket Cost	\$405.00	\$248.67

GLASS

Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total List Cost
Glass Area (Adjusted)	N/A	10.42 sqft	\$109.38	\$109.38
		Total Glass Cost	\$109.38	\$109.38

FABRICATION

Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total List Cost
Joints Fabrication Labor	N/A	24.00 joints	\$360.00	\$360.00
		Total Fabrication Cost	\$360.00	\$360.00

Elevation One

System Input

Item	Value
System Input	YES 45TU FRONT SET(OG)
Finish	Clear
Elevation Type	Elevation One
Total Count	2.00
Bays Wide	4.00
Bays Tall	2.00
Custom Bay Widths	10.00 in, 44.67 in, 44.67 in, 44.67 in
Custom Bay Heights	48.00 in, 48.00 in
Opening Width	144.00 in

Item	Value
Opening Height	96.00 in
Sq Ft per Type	96.00 sqft
Total Sq Ft	192.00 sqft
Perimeter Ft	40.00 ft
Total Perimeter Ft	80.00 ft
Doors	None

PROFILES

Description	Part Number	Total Quantity Required	Quantity Per Elevation	Total List Cost	Total List Cost Per Elevation	Discounted Total List Cost	Discounted Total List Cost Per Elevation
Vertical Sill/Jamb Screw Spline Assembly (Jamb) / Horizontal Sill/Jamb Screw Spline Assembly (Sill)	BE9-2513	8ft, 8ft, 8ft, 8ft, 0.83ft, 3.72ft, 3.72ft, 3.72ft, 0.83ft, 3.72ft, 3.72ft, 3.72ft	0.83ft x 1, 3.72ft x 3, 8ft x 2	\$1,257.00	\$838.00	\$771.80	\$514.53
Vertical Flush Filler	E9-2512	8ft x 6	8ft x 3	\$300.00	\$150.00	\$184.20	\$92.10
Vertical Two Piece Mullion Screw Spline Assembly	BE9-2511	8ft x 6	8ft x 3	\$994.00	\$497.00	\$610.32	\$305.16
Horizontal Horizontal Screw Spline Assembly	BE9-2515	0.83ft, 3.72ft, 3.72ft, 3.72ft, 0.83ft, 3.72ft, 3.72ft, 3.72ft	0.83ft x 1, 3.72ft x 3	\$1,054.00	\$527.00	\$647.16	\$323.58
Horizontal Head	BE9-2514	0.83ft, 3.72ft, 3.72ft, 3.72ft, 0.83ft, 3.72ft, 3.72ft, 3.72ft	0.83ft x 1, 3.72ft x 3	\$888.00	\$444.00	\$545.23	\$272.62
Thermal Sill Flashing	BE9-2578	12ft x 2	12ft x 1	\$264.00	\$264.00	\$162.10	\$162.10
Horizontal Glass Stop (Use with BE9-2514, BE9-2515, BE9-2517)	E9-2519	0.83ft, 3.72ft, 3.72ft, 3.72ft, 0.83ft, 3.72ft, 3.72ft, 3.72ft, 0.83ft, 3.72ft, 3.72ft, 3.72ft	0.83ft x 2, 3.72ft x 6	\$255.15	\$170.10	\$156.66	\$104.44
			Total Profile Cost	\$5,012.15	\$2,890.10	\$3,077.46	\$1,774.52

ACCESSORIES

Description	Part Number	Total Quantity Required	Quantity Per Elevation	Total List Cost	Total List Cost Per Elevation	Discounted Total List Cost	Discounted Total List Cost Per Elevation
End Dam For Sill Flashing	E1-0199	4.00 pcs	2.00 pcs	\$64.80	\$64.80	\$39.79	\$39.79
Water Deflector	E2-0047	16.00 pcs	8.00 pcs	\$119.00	\$119.00	\$73.07	\$73.07
#12 x 1-1/4" PHSMS Type AB, Zinc Plated Steel, For Screw Spline Attachment	PC-1220	112.00 pcs	56.00 pcs	\$36.60	\$18.30	\$22.47	\$11.24
#10-24 x 3/8" PHMS, Stainless Steel, For Attachment of Sill to Sill Flashing	PM-1006-SS	24.00 pcs	12.00 pcs	\$46.65	\$46.65	\$28.64	\$28.64
#12 x 3/4" UFHSMS Type A, Zinc Plated Steel For End Dam Attachment	UA-1212	8.00 pcs	4.00 pcs	\$48.60	\$48.60	\$29.84	\$29.84
Setting Block Chair Use with E2-0177 Setting Block at Sill	E1-2530	16.00 pcs	8.00 pcs	\$72.00	\$36.00	\$44.21	\$22.10
Setting Block For Sill	E2-0177	16.00 pcs	8.00 pcs	\$76.95	\$76.95	\$47.25	\$47.25
1-1/8" "W" Side Block For Jamb	E2-0545	8.00 pcs	4.00 pcs	\$147.00	\$147.00	\$90.26	\$90.26
1/2" "W" Side Block For Intermediate Vertical Deep Pocket	E2-0154	12.00 pcs	6.00 pcs	\$56.70	\$56.70	\$34.81	\$34.81
Setting Block For Intermediate Horizontal	E2-0611	16.00 pcs	8.00 pcs	\$95.25	\$95.25	\$58.48	\$58.48
			Total Accessory Cost	\$840.50	\$786.20	\$516.07	\$482.73

GASKETS

Description	Part Number	Total Quantity Required	Quantity Per Elevation	Total List Cost	Total List Cost Per Elevation	Discounted Total List Cost	Discounted Total List Cost Per Elevation
Glazing Gasket For 1" Glazing	E2-0052	448.00 ft	448.00 ft x 1	\$405.00	\$405.00	\$248.67	\$248.67
			Total Gasket Cost	\$405.00	\$405.00	\$248.67	\$248.67

GLASS

Description	Part Number	Total Quantity Required	Quantity Per Elevation	Total List Cost	Total List Cost Per Elevation	Discounted Total List Cost	Discounted Total List Cost Per Elevation
Glass Area (Adjusted)	N/A	167.50 sqft	83.75 sqft	\$1,758.75	\$879.38	\$1,758.75	\$879.38
			Total Glass Cost	\$1,758.75	\$879.38	\$1,758.75	\$879.38

FABRICATION

Description	Part Number	Total Quantity Required	Quantity Per Elevation	Total List Cost	Total List Cost Per Elevation	Discounted Total List Cost	Discounted Total List Cost Per Elevation
Joints Fabrication Labor	N/A	48.00 joints	24.00 joints	\$720.00	\$360.00	\$720.00	\$360.00
			Total Fabrication Cost	\$720.00	\$360.00	\$720.00	\$360.00

SUMMARY

PROFILES

Description	Project Total Materials	Total Feet Required	Sticks Required	Total Quantity Required	Total List Cost	Discounted Total List Cost	Residual Material Quantity	Residual Waste %
Vertical Sill/Jamb Screw Spline Assembly (Jamb)	BE9-2513 (clear)	56.00 ft	3 (24ft per)	8ft x4, 4ft x6, 1ft x2	\$1,257.00	\$771.80	15.72ft x1, 0.28ft x1	22.22%
Vertical Flush Filler	E9-2512 (clear)	48.00 ft	2 (24ft per)	8ft x6	\$300.00	\$184.20	0.00 ft	0.00%
Vertical Two Piece Mullion Screw Spline Assembly	BE9-2511 (clear)	48.00 ft	2 (24ft per)	8ft x6	\$994.00	\$610.32	0.00 ft	0.00%
Horizontal Horizontal Screw Spline Assembly	BE9-2515 (clear)	24.00 ft	2 (24ft per)	4ft x6, 1ft x2	\$1,054.00	\$647.16	23.17ft x1, 0.83ft x1	50.00%
Horizontal Head	BE9-2514 (clear)	24.00 ft	2 (24ft per)	4ft x6, 1ft x2	\$888.00	\$545.23	23.17ft x1, 0.83ft x1	50.00%
Thermal Sill Flashing	BE9-2578 (clear)	24.00 ft	1 (24ft per)	12ft x2	\$264.00	\$162.10	0.00 ft	0.00%
Horizontal Glass Stop (Use with BE9-2514, BE9-2515, BE9-2517)	E9-2519 (clear)	48.00 ft	3 (24ft per)	4ft x12, 1ft x4	\$255.15	\$156.66	22.33ft x1, 0.83ft x2	33.33%
Vertical Sill/Jamb Screw Spline Assembly (Jamb)	BE9-2513 (black)	14.08 ft	1 (24ft per)	6ft x2, 2ft x1, 1ft x1, 0ft x1	\$460.90	\$282.99	9.92ft x1	41.32%
Vertical Flush Filler	E9-2512 (black)	11.33 ft	1 (24ft per)	6ft x2	\$165.00	\$101.31	12.67ft x1	52.78%
Vertical Two Piece Mullion Screw Spline Assembly	BE9-2511 (black)	11.33 ft	1 (24ft per)	6ft x2	\$546.70	\$335.67	12.67ft x1	52.78%
Horizontal Horizontal Screw Spline Assembly	BE9-2515 (black)	2.75 ft	1 (24ft per)	2ft x1, 1ft x1, 0ft x1	\$579.70	\$355.94	21.25ft x1	88.54%
Horizontal Head	BE9-2514 (black)	2.75 ft	1 (24ft per)	2ft x1, 1ft x1, 0ft x1	\$488.40	\$299.88	21.25ft x1	88.54%
Thermal Sill Flashing	BE9-2578 (black)	2.75 ft	1 (24ft per)	3ft	\$290.40	\$178.31	21.25ft x1	88.54%
Horizontal Glass Stop (Use with BE9-2514, BE9-2515, BE9-2517)	E9-2519 (black)	8.25 ft	1 (24ft per)	2ft x3, 1ft x3, 0ft x3	\$93.56	\$57.44	15.75ft x1	65.62%
				Total Profile Cost	\$7,636.80	\$4,689.00		

ACCESSORIES

Description	Project Total Materials	Total Pieces Required	Quantity Per Order	Orders Required	Total List Cost	Discounted Total List Cost	Residual Material Quantity	Residual Waste %
End Dam For Sill Flashing	E1-0199	6.00 pcs	20 pcs per	1 order	\$64.80	\$39.79	14.00 pcs	70.00%
Water Deflector	E2-0047	22.00 pcs	50 pcs per	1 order	\$119.00	\$73.07	28.00 pcs	56.00%
#12 x 1-1/4" PHSMS Type AB, Zinc Plated Steel, For Screw Spline Attachment	PC-1220	172.00 pcs	100 pcs per	2 orders	\$36.60	\$22.47	28.00 pcs	14.00%
#10-24 x 3/8" PHMS, Stainless Steel, For Attachment of Sill to Sill Flashing	PM-1006-S S	33.00 pcs	100 pcs per	1 order	\$46.65	\$28.64	67.00 pcs	67.00%
#12 x 3/4" UFHSMS Type A, Zinc Plated Steel For End Dam Attachment	UA-1212	12.00 pcs	100 pcs per	1 order	\$48.60	\$29.84	88.00 pcs	88.00%
Setting Block Chair Use with E2-0177 Setting Block at Sill	E1-2530	22.00 pcs	1 pcs per	22 orders	\$99.00	\$60.79	0.00 pcs	0.00%
Side Block For Intermediate Vertical Shallow Pocket	E2-0166	18.00 pcs	50 pcs per	1 order	\$76.95	\$47.25	32.00 pcs	64.00%
Setting Block For Sill	E2-0177	22.00 pcs	50 pcs per	1 order	\$76.95	\$47.25	28.00 pcs	56.00%
1-1/8" "W" Side Block For Jamb	E2-0545	14.00 pcs	50 pcs per	1 order	\$147.00	\$90.26	36.00 pcs	72.00%
1/2" "W" Side Block For Intermediate Vertical Deep Pocket	E2-0154	18.00 pcs	50 pcs per	1 order	\$56.70	\$34.81	32.00 pcs	64.00%
Setting Block For Intermediate Horizontal	E2-0611	22.00 pcs	50 pcs per	1 order	\$95.25	\$58.48	28.00 pcs	56.00%
				Total Accessory Cost	\$867.50	\$532.64		

GASKETS

Description	Project Total Materials	Total Feet Required	Rolls Required	Total Quantity Required	Total List Cost	Discounted Total List Cost	Residual Material Quantity	Residual Waste %
Glazing Gasket For 1" Glazing	E2-0052 (clear)	448.00 ft	1 (500ft per)	448ft	\$405.00	\$248.67	52ft x1	10.40%
Glazing Gasket For 1" Glazing	E2-0052 (black)	101.00 ft	1 (500ft per)	101ft	\$405.00	\$248.67	399ft x1	79.80%

Description	Project Total Materials	Total Feet Required	Rolls Required	Total Quantity Required	Total List Cost	Discounted Total List Cost	Residual Material Quantity	Residual Waste %
				Total Gasket Cost	\$810.00	\$497.34		

GLASS

Description	Project Total Materials	N/A	Unit Price	Total Quantity Required	Total List Cost	Discounted Total List Cost	Residual Material Quantity	Residual Waste %
Glass Area (Adjusted)	Glass Area (Adjusted)	N/A	\$10.50	177.92 sqft	\$1,868.12	\$1,868.12	N/A	N/A

LABOR

Description	Project Total Materials	N/A	Unit Price	Total Quantity Required	Total List Cost	Discounted Total List Cost	Residual Material Quantity	Residual Waste %
Joints Fabrication Labor	Joints Fabrication Labor	N/A	\$15.00	72.00 joints	\$1,080.00	\$1,080.00	N/A	N/A
				Total Labor Cost	\$1,080.00	\$1,080.00		

ELEVATION SUMMARY

Elevation Name

Item	Value
Elevation One	144.0" x 96.0"
Elevation 2	33.0" x 68.0"

TOTAL

COST OVERVIEW

Item	Value
List Price Total:	\$12,262.43
Discounted Total:	\$8,667.11
Residual/Waste Cost:	\$2,462.10
Waste Percentage:	28.41%
MISCELLANEOUS COSTS	
Overhead Materials	\$86.67
Overhead Labor	\$173.34
Admin and Management	\$260.01
Engineering	\$346.68
Packaging Materials	\$433.36
Shipping and Transport	\$520.03
Commissions	\$606.70
SUBTOTAL	\$2,426.79
MARKUPS / PROFIT	
Profit on Material	\$457.52
Profit on Waste	\$221.59
Profit on Glass Purchase	\$186.81
Profit on Wages	\$118.80
Planning / Technical Office	\$1,040.05
Commission	\$1,126.72
SUBTOTAL	\$3,151.50

PROJECT TOTAL

Item	Value
Discounted Total:	\$8,667.11
+ Miscellaneous:	\$2,426.79
+ Markups:	\$3,151.50

GRAND TOTAL:

Item	Value
GRAND TOTAL:	\$14,245.40

Project Cost Breakdown

