

PROJECT ESTIMATION REPORT

Project: Test Report

Date: January 15, 2026

System Input	YES 45TU FRONT SET(OG)			PROFILES				
Finish	Clear			Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total List Cost
Elevation Type	1			Vertical Sill/Jamb Screw Spline Assembly (Jamb) / Horizontal Sill/Jamb Screw Spline Assembly (Sill)	BE9-2513	8ft, 8ft, 3ft, 3ft, 3ft, 3ft	\$838.00	\$514.53
Total Count	1.00			Vertical Flush Filler	E9-2512	8ft x 3	\$150.00	\$92.10
Bays Wide	4.00			Vertical Two Piece Mullion Screw Spline Assembly	BE9-2511	8ft x 3	\$497.00	\$305.16
Bays Tall	2.00			Horizontal Horizontal Screw Spline Assembly	BE9-2515	3ft x 4	\$527.00	\$323.58
Custom Bay Widths	Equal distribution			Horizontal Head	BE9-2514	3ft x 4	\$444.00	\$272.62
Custom Bay Heights	Equal distribution			Thermal Sill Flashing	BE9-2578	12ft	\$264.00	\$162.10
Opening Width	144.00 in			Horizontal Glass Stop (Use with BE9-2514, BE9-2515, BE9-2517)	E9-2519	3ft x 8	\$85.05	\$52.22
Opening Height	96.00 in					Total Profile Cost	\$2,805.05	\$1,722.30

Sq Ft per Type	96.00 sqft			ACCESSORIES				
Total Sq Ft	96.00 sqft			Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total List Cost
Perimeter Ft	40.00 ft			End Dam For Sill Flashing	E1-0199	2.00 pcs	\$64.80	\$39.79
Total Perimeter Ft	40.00 ft			Water Deflector	E2-0047	8.00 pcs	\$119.00	\$73.07
Doors	None			#12 x 1-1/4" PHSMS Type AB, Zinc Plated Steel, For Screw Spline Attachment	PC-1220	56.00 pcs	\$18.30	\$11.24
				#10-24 x 3/8" PHMS, Stainless Steel, For Attachment of Sill to Sill Flashing	PM-1006-S S	12.00 pcs	\$46.65	\$28.64
Bay Distribution Diagram	*Note - C/L Dimensions			#12 x 3/4" UFHSMS Type A, Zinc Plated Steel For End Dam Attachment	UA-1212	4.00 pcs	\$48.60	\$29.84
				Setting Block Chair Use with E2-0177 Setting Block at Sill	E1-2530	8.00 pcs	\$36.00	\$22.10

Bay Distribution Layout

B1 36.0" x 48.0"	B2 36.0" x 48.0"	B3 36.0" x 48.0"	B4 36.0" x 48.0"
B5 36.0" x 48.0"	B6 36.0" x 48.0"	B7 36.0" x 48.0"	B8 36.0" x 48.0"

Total: 144.0" W x 96.0" H

				Setting Block For Sill	E2-0177	8.00 pcs	\$76.95	\$47.25
				1-1/8" "W" Side Block For Jamb	E2-0545	4.00 pcs	\$147.00	\$90.26
				1/2" "W" Side Block For Interme diate Vertical Deep Pocket	E2-0154	6.00 pcs	\$56.70	\$34.81
				Setting Block For In termediate Horizontal	E2-0611	8.00 pcs	\$95.25	\$58.48
						Total Accessory Cost	\$786.20	\$482.73
				GASKETS				
				Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total List Cost
				Glazing Gasket For 1" Glazing	E2-0052	224.00 ft	\$405.00	\$248.67

						Total Gasket Cost	\$405.00	\$248.67
				GLASS				
				Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total List Cost
				Glass Area (Adjusted)	N/A	83.75 sqft	\$879.38	\$879.38
						Total Glass Cost	\$879.38	\$879.38
				FABRICATI ON				
				Description	Part Number	Total Quantity Required	Total List Cost	Discounted Total List Cost
				Joints Fabrication Labor	N/A	24.00 joints	\$360.00	\$360.00
						Total Fabrication Cost	\$360.00	\$360.00
						COST/ELE VATION		TOTAL ELE VATION COST
						PROFILE COSTS		\$1,722.30
						ACCESSO RY COSTS		\$482.73
						GASKET COSTS		\$248.67
						GLASS COSTS		\$879.38
						FABRICATI ON COSTS		\$360.00
						1 TOTAL COSTS		\$3,693.07
						*Note - Elevation costs based on discounted material costs		